






Baglioni Headquarters

Via Dante Alighieri, 8
28060 San Pietro Mosezzo (NO)
Italy
Tel. +39 0321485211

SALES CONTACT

sales@baglionispa.com

ENGINEERING CONTACT

tecnico@baglionispa.com

QUALITY CONTACT

quality@baglionispa.com

THE GROUP

The companies of Baglioni SpA manufacture carbon and stainless-steel pressure equipment used for storage and process in the Compressed-air and Oil&Gas applications.

Baglioni Group consists of four companies located in EUROPE, USA and CHINA.

MPV MORGANTON

Our MPV LLC plant in Marion, North Carolina, is specialized in the manufacture of pressure vacuum tanks for medical applications as well as special pressure vessels.

BAGLIONI HEADQUARTERS

ASTRA

ASTRA is organized into three divisions SPE, SPV and OIL & GAS. ASTRA specializes in the design and construction of tanks, heat exchangers, columns, condensers, etc. for the chemical, petrochemical and energy sectors.

CSC

Our C.S.C. production unit is specialized in the manufacture of pressure equipment and vacuum tanks. It manufactures certified tanks for installation sites all over the world.

AIRCOM

AIRCOM is specialized in the manufacture of pressure tanks with a capacity range from 0,9 lt and 600 lt.

The main mission of our production facilities in China is to supply the Asian and Pacific markets with top-quality products at competitive prices.



ASTRA REFRIGERANTI SRL

OIL & GAS

Via Meucci, 1
28066 Galliate (NO) Italy
Tel. +39 0321 808011

AIR COM VESSELS

Via Villata, 2 - 28060
Casalvolone (NO) Italy
Tel. +39 0161 315494

AIR COM SPECIAL PRESSURE EQUIPMENT

Via Leopardi, 27- 28060
San Pietro Mosezzo (NO) Italy
Tel. +39 0321 485611



COINOX VESSELS

SS.16 KM 977+400
73022 Corigliano
d'Otranto (LE) Italy
Tel. +39 0836 471239



CSC SRL

Strada Cacciolo, 34
15030 TERRUGGIA (AL) Italy
Tel. +39 0142 403055



MPV MORGANTON PRESSURE VESSELS LLC SPECIAL PRESSURE EQUIPMENT

1 Alfredo Baglioni Drive
MARION NC 28752 USA
Tel. +1 (828) 6523704



AIRCOM (ZHEJIANG) GENERAL EQUIPMENT CO. LTD

No.968 Waitang Road (Haiyan Economic Development Zone), Xitangqiao Subdistrict, Haiyan County, Jiaxing City, Zhejiang Province, China, 314305 - Tel. +86 573 86862233

TABLE OF CONTENTS

6	Certifications
8	Finishing
10	Declaration of conformity
11	Instructions for use and maintenance
12	Fitness declaration

-10°C AIR VESSELS

14	Small size Vertical - Painted Galvanized
15	Small size Horizontal - Painted Galvanized
16	Horizontal - Painted
17	Horizontal - Galvanized ALM
18	Horizontal with plate
19	Vertical - Painted 11-12-16 bar
20	Vertical - Galvanized 11-12-16 bar
21	Vertical - ALM 11-12-16 bar
22	Vertical Vacuum - Painted
23	Vertical Autoclave - Galvanized

-20°C AIR VESSELS

25	Vertical - Painted 11-12-16 bar -20°C
26	Vertical - Galvanized ALM -20°C
27	Vertical for Oxygen
28	Vertical Oversize - Painted
29	Vertical Oversize - Galvanized ALM
30	Horizontal Oversize - Painted Galvanized ALM
31	Flanged connections and non-mandatory inspection openings

HIGH PRESSURE VESSELS

33	Vertical 21 bar - Painted Galvanized
34	Vertical 32 bar - Painted Galvanized
35	Vertical 42 bar - Painted Galvanized
36	ASME

STAINLESS STEEL VESSELS

38	Vertical - AISI 304 AISI 316L
39	Horizontal - AISI 304 AISI 316L
40	Accessories
42	Special projects



GLOBAL DESIGN

Our engineering develops the projects and adapts them to the in force regulations on an international scale to keep the same standard of production for all factories in the three continents.



MULTI APPROVAL

According to geographical areas and customer's specification we design products in compliance with dedicated approvals and, if necessary, simultaneous certifications.



CUSTOMIZED LOGISTICS

Flexibility to adapt to customer's needs through the management of specific logistics according to the product type.

CO-DESIGN

Innovative solutions and our know-how are at the customer's disposal to develop a design that aims to optimize the product on an industrial scale and to obtain the best technical and economical results.



LOCAL PRODUCTION

Our main goal is to minimize both production and transport costs by producing locally and covering the whole range of products, from standard to custom made.



FINISHING

The knowledge of materials and their employment in various applications allows us to offer a wide range of finishing, an important added value for the customization of products.



CERTIFICATIONS



Our products are designed and manufactured in compliance with the applicable EU Directives or according to the major international standards.



SPVD 2014/29/UE Directive (ex 2009/105/EC)
Simple Pressure Vessels Directive

PED 2014/68/UE Directive (ex 97/23/EC)
Pressure Equipment Directive

ASME Sect. VIII Div. 1 / Div. 2

National Board Registration

Canadian Registration Number (CRN)

Australian Standard AS1210

MOM Singapore Regulation

DOSH Malesia Regulation

Consular Visa
• Tunisia • Morocco

Manufacture License of Special Equipment
People's Republic of China D1/D2 - A1/A2

MHLW Japan Regulation

Israeli Standard Regulation

- Marine Registration
- » ABS American Bureau of Shipping
 - » DNV Det Norske Veritas
 - » B.V. Bureau Veritas
 - » LRS Lloyd's Register of Naval Ship
 - » RINA Services
 - » GL Germanischer Lloyd
 - » NK Nippon Kaiji Kyokai
 - » CCS China Classification Society
 - » RMRS Russian Maritime Register of Shipping
 - » KR Korean Register of Shipping

EAC TRCU032 RUSSIA

 RAL 1004
Smooth Finish

 RAL 3000
Smooth
Textured Finish

 RAL 5002
Smooth Finish

 RAL 5005
Textured Finish

 RAL 5010
Smooth Finish

 RAL 5015
Smooth
Textured Finish

 RAL 7011
Textured Finish

 RAL 7016
Smooth
Textured Finish

 RAL 7021
Smooth
Textured Finish

 RAL 7024
Textured Finish

 RAL 7035
Textured Finish

 RAL 7036
Textured Finish

 RAL 7040
Textured Finish

 RAL 7042
Textured Finish

 RAL 7043
Smooth Finish

 RAL 9002
Textured Finish



POWDER COATING

External surface treatment performed on all standard vessels.

After an accurate surface preparation through chemical wash-down or sandblasting, the product is transferred to dedicated booths where powder paint is sprayed by means of electrostatic or triboelectric spray guns. The processed product is then baked in curing ovens.

HOT-DIP GALVANIZATION

Internal and external treatment for carbon steel vessels.

Hot-dip galvanizing is the main method used to protect steel against weather conditions and is performed by dipping vessels in a molten zinc bath. During this metallurgical process, the surface composition changes into an intercrystalline zinc-steel alloy that forms an extremely resistant, long-lasting anti-corrosion coating. The thickness of the protection depends on material type, dipping time and zinc bath temperature.

SURFACE ELECTROPOLISHING TREATMENT

This surface treatment electrolytically removes all metal particles in order to reduce roughness.

This process is essential when corrosion-resistance and cleanliness requirements are particularly strict (e.g., for pharmaceutical, chemical, biochemical and food products).

FINISHING

ALM PAINTING

This treatment is specific for tank interiors and is performed by applying special protective paints that ensure high resistance to corrosive agents over time.

Raw vessels first undergo chemical washing and pickling and are then sprayed with thermosetting epoxy resin before completing the process with the final baking stage in the oven. The ALM treatment is certified pursuant to Ministerial Decree dated 21 March 1973 and subsequent amendment dated 6 April 2004, governing the hygiene of food-grade containers containing substances for personal use.

PICKLING AND PASSIVATION

Internal and external treatment for stainless steel vessels.

Pickling is essential to remove the oxide particles produced during the various processing stages. There are two types of pickling systems: mechanical and chemical. The former is performed with silica sand or stainless-steel brushes, the latter by dipping the item into an acid solution. The subsequent passivation dissolves and removes any contaminants from the surface, thus recreating the protective layer.

FOOD-GRADE AND PHARMACEUTICAL TREATMENT

Performed after pickling and passivation.

This special treatment is performed in compliance with ASTM A380 regulation.

This certificate shall be duly kept to be submitted to inspection authorities during periodical audits as specified by the applicable regulations.

FOR INQUIRIES CONCERNING DECLARATION OF CONFORMITY PLEASE CONTACT
quality@baglionispa.com

Instructions for a proper use and maintenance of the vessels are found on page 2 of the Dec. of conf. A strict attention of this instructions will ensure the lifespan and safe use of the vessels. The parameters displayed at the bottom of this sheet are of the utmost importance to this purpose:

- » Rating (A): refers to design pressure (bar) as well as the pressure limit for vessel use. This rate is found both on the name plate and the Declaration of Conformity.
- » Rating (B): refers to shell thickness (mm) below which the vessel can no longer be kept in operation
- » Rating (C): refers to formed heads thickness (mm) below which the vessel can no longer be kept in operation

It is extremely important that ratings (B) and (C) are tested regularly because water, gas or bacterial reactions may cause natural corrosion phenomena which will determine the deterioration of materials and eventually jeopardize the product's performance.

CE

• Dichiariamo, sotto la nostra responsabilità, che il serbatoio nuovo qui descritto:
Nous déclarons, sous notre seule responsabilité, que le récipient neuf décrit ci après:
 We hereby declare under our own responsibility, that the pressure vessel described hereunder:
Declaramos, bajo nuestra única responsabilidad, que el recipiente nuevo descrito aquí:
 Unter unserer Verantwortung erklären wir hiermit, daß der neue unten beschriebene Druckluftbehälter:

N.F.:	Capacità:	LOTTO N.:	Anno di fabbricazione:
N.F.:	Volume:	LOT N.:	Année de fabrication:
Manufacturing N.:	Capacity:	Lot inspection:	Anno di costruzione:
Matricula N.:	Capacidad:	Lot: N.:	Año de fabrication:
Bau-Nr.:	Inhalt:	Losprüfung:	Baujahr:
De 9491			
A 9526	Lt. 500	03/09	2009
Famiglia:	Pressione di servizio/Calcolo:	Variant:	Temperatura di servizio:
Famille:	Pression de service/Calcul:	Variant:	Temperature de service:
Family:	Operating pressure/Calculation:	Type:	Operating temperature:
Familia:	Presión de servicio/Calculación:	Variación:	Temperatura de servicio:
Familie:	Betriebsüberdruck/Berechnungsdruk:	Typ:	Betriebstemperatur:

È CONFORME ALLE DISPOSIZIONI DELLA DIRETTIVA CEE 87/404 RELATIVA AI RECIPIENTI SEMPLICI A PRESSIONE
EST CONFORME AUX DISPOSITIONS DE LA DIRECTIVE 87/404 CEE RELATIVE AUX RECIPIENTS A PRESSION SIMPLES
COMPLIES WITH ECC DIRECTIVE 87/404 CONCERNING SIMPLE PRESSURE VESSELS
ES CONFORME A LAS DISPOSICIONES DE LA NORMATIVA CEE 87/404 RELATIVA A LOS RECIPIENTES A PRESSION VOPRICHEN
DEN VORSCHRIFTEN EG-RICHTLINIE 87/404 ÜBER EINFACHE DRUCKBEHÄLTER ENTSPRICHT

* che al modello della famiglia e sue varianti alla quale questo serbatoio appartiene è stata riconosciuta una:
que le modèle de la famille et ses variantes à laquelle appartient ce récipient a fait l'objet de la délivrance d'une:
 that the family type and its variations, which this vessel is part of, has received:
 que el modelo de la familia y sus tipos al que pertenece este recipiente ha sido el objeto de la deliberación de una:
 da) der betreffende Behältertyp mit:

ATTESTAZIONE D'ESAME DEL TIPO N°	<u>07.72226/C/PS</u>	DEL	<u>18/10/07</u>	REV.	<u>18/10/07</u>	rilasciata da CPM, organismo notificato n°I-0398
ATTESTATION D'EXAMEN CE DE TYPE N°	<u>07.72226/C/PS</u>	DU	<u>18/10/07</u>	M.J.	<u>18/10/07</u>	delivrée par la CPM, organisme notifié n°I-0398
ECC TYPE EXAMINATION CERTIFICATE N°	<u>07.72226/C/PS</u>	DATED	<u>18/10/07</u>	REV.	<u>18/10/07</u>	issued by CPM, official test body n°I-0398
CERTIFICACION DE EXAMEN CE DE TIPO N°	<u>07.72226/C/PS</u>	DEL	<u>18/10/07</u>	REV.	<u>18/10/07</u>	expedido por CPM, organismo notificado n°I-0398
EG-BAUMUSTERPRÜFUNG NR.	<u>07.72226/C/PS</u>	VOM	<u>18/10/07</u>	REV.	<u>18/10/07</u>	von anerkannter Prüfstelle CPM, n°I-0398 geprüft wurde

* che questo serbatoio ha superato una prova idraulica a una Pressione di Prova uguale a 1,5 volte la pressione di calcolo.
que ce récipient a subi avec succès un essai hydraulique à une Pression d'Épreuve égale à 1,5 fois la Pression de calcul.
that the aforementioned pressure vessel passed the hydraulic test when submitted to a test pressure equal to 1,5 times the design pressure.

* este recipiente ha superado con seguridad una prueba hidráulica a una presión igual a 1,5 veces la presión de cálculo.
dass obige Behälter die Wasserdruckprobe bestanden hat, wobei der Proberdruck 1,5 mal der Nenndruck entsprach.

* che l'Organismo notificato ha apposto una punzonatura di identificazione (cuore APAVE) sulla targa del costruttore
que l'Organisme notifié a apposé un poinçon d'identification (cœur APAVE) sur la plaque constructeur.
that the notified institution has applied a marking punch on the name plate.
daß die anerkannte Prüfstelle einen Kennzeichnungsmempel auf das Herstellerschild gestempelt hat.

Terruggia, il 2/7/2009

Il Costruttore – Le Constructeur – The Manufacturer
El constructor – Der Hersteller



Pagina 1 di 2

	NOTICES OF INSTRUCTION L'installateur a pression est destiné à l'accumulation d'air comprimé et ne doit pas être soumis à de rapides fluctuations de pression. L'utilisation adéquate de l'appareil à air comprimé est une condition préalable essentielle pour en garantir la sécurité. Dans ce but l'utilisateur doit: 1) employer l'appareil de façon appropriée dans les limites doubles de pression et de température de service qui sont indiquées sur la plaque du constructeur. 2) éviter d'effectuer des soudures sur les parties à pression. 3) utiliser l'air de l'appareil sans coupleur de sécurité (coupleur de sécurité et pressostat) et si possible (manomètre) efficace et contrôler si et/ou le remplacement, en cas de nécessité, par d'autres organes ayant des caractéristiques équivalentes, après en avoir informé le constructeur. En particulier, la sécurité du support de câble doit être appliquée directement sur le réservoir sans possibilité d'extrusion, sauf avoir une capacité de décharge supérieure à la moitié d'air qui peut être admise dans le réservoir, être tarée et plombée à la pression de (A) bar. Sur la manomètre, l'ordre de pression de (A) bar doit être indiqué par un trait rouge. 4) Éviter autant que possible de placer l'appareil dans des locaux qui ne sont pas spécialement adaptés; l'accumulation d'air dans des zones exposées à des sources de chaleur ou à proximité de substances inflammables. 5) éviter tout entraînement l'appareil de valeurs élastiques sur les supports inférieurs et quelque soit le modèle (frein ou mobile) pendant son utilisation de façon à éviter des vibrations qui pourraient provoquer des ruptures par fatigue. Ne pas faire le récipient ou des parties montées sur le récipient au sud ou des parties fixes (colonne...). .. 6) Prévenir la corrosion, ne pas le mouvoir, des conditions peuvent d'accumuler dans les réservoirs, ceux-ci doivent être purgés tous les jours. Cela peut se faire manuellement en ouvrant la purge de sécurité ou par un purgateur automatique monté sur le réservoir. Dans le cas de la technique d'entretien, le service après-vente habilité, doit vérifier la formation éventuelle de corrosion à l'intérieur et effectuer un contrôle extérieur à intervalles annuels. Si le réservoir est utilisé avec un compresseur sans, dans un ambiant fortement humide, ou dans des conditions d'humidité (faible ventilation, vapeur aqueuse ...) le contrôle visuel doit se faire à plus fréquemment. L'opérateur efficace de réservoir pour corrosion ne devra pas être inférieure à (B) mm pour la visière et (C) mm pour les fonds. 7) Agir en tant que chef de file pour la protection de manière adéquate au cas échéant. NOTES MANIPULATION ET UTILISATION D'IMPROPRIÉTÉ DE L'APPAREIL, SANS FORMULEMENT INTÉRESSÉ. Respecter l'utilisateur que dans tous les cas, et le titre de respecter la législation sur l'utilisation des appareils à pression de l'Etat ou son fait usage. INSTRUCTION FOR USE OF COMPRESSED AIR VESSEL. The pressure vessel is intended to be used for the storage of compressed air and shall not be subject to rapid fluctuations of pressure. To ensure operation of compressed air vessel under safe conditions, the proper use of same must be guaranteed. To this purpose, the user should proceed as follows: 1) Use the vessel properly, within the pressure and temperature limits stated on the nameplate and on the testing report, which must be kept with care; 2) welding on the vessel is forbidden; 3) ensure that the vessel is completely safe with suitable and adequate safety and control fittings and replace them with equivalent ones in case of necessity, prior to the Manufacturer's consent. In particular, the safety valve must be applied directly to the vessel, have a discharge capacity higher than the air intake and be set and loaded at a pressure of (A) bar. The pressure value of (A) bar on the pressure gauge must be indicated with a red line. 4) avoid, if it is possible, to store the vessel in heavily ventilated rooms. After scrupulously to store the vessel near heating sources or inflammable substances; 5) avoid the pressure vessel with vibrations directed to avoid possible fatigue failure caused by vibration of the vessel during use. Do not anchor the vessel or attached components to the ground or fixed structures (columns...). 6) Corrosion must be prevented depending on the conditions of use, condensation may accumulate inside the tank, and this must be emptied out every day. This can be done manually, by opening the draining tap, or by means of the automatic condensation control, if fitted to the tank. During maintenance, every 12 months, the user or a Client Service expert must check the presence of internal corrosion and perform an annual visual control, if the vessel is used with an air compressor, or in the presence of humidity, or in adverse conditions (poor ventilation, corrosion agents...), the inspections should be made more frequently. The actual wall thickness of the tank after corrosion should not be smaller than (B) mm for the shell and (C) mm for the heads 7) proceed similarly with safety, according to the existing provisions. TAMPERING AND IMPROPER USE OF THE TANK ARE FORBIDDEN. The users must comply with the laws on the operation of pressure equipment in force in the relative countries.	UTZERRANWEISUNGEN Der Behälter ist bestimmt zur Speicherung von Druckluft. Seine Auslegung erfolgt für überlegende statischen Belastung. Die korrekte Bedienung des Druckbehälters ist eine unabdingbare Voraussetzung, um die Sicherheit zu gewährleisten. Zu diesem Zweck sollte der Anwender die folgenden Schritte beachten: 1) den Druckbehälter innerhalb der Neuse-Druck und Temperaturgrenzen verwenden, die auf dem Schild und in der Konformitätserklärung angegeben sind, die mit der größten Sorgfalt zu befolgen ist; 2) keine Schweißarbeiten auf dem Druckbehälter durchführen; 3) sich vergewissern, dass der Behälter mit dem Druckluftsystem mit der richtigen Art der Ausrüstung mit der richtigen Art der Ausrüstung verbunden ist, und die Ausrüstung mit dem Hersteller zu ersetzen werden, falls erforderlich, bevor die Ausrüstung mit dem Druckluftsystem verbunden wird, eine höhere Absicherungsstufe als der Luftbehälter haben und auf einen Druck von (A) bar begrenzt und plombiert werden. Auf dem Druckmesser muss der Druckwert von (A) bar in Rot gekennzeichnet sein; 4) möglichst vermeiden, dass der Druckbehälter in schlecht belüfteten Räumen aufgestellt wird; sorgfältig vermeiden, dass der Behälter Wärmegelenken oder entflammenden Substanzen ausgesetzt wird; 5) vermeiden Sie mit Vibrationen verbunden, um eine Ermüdungsrisikoprüfung zu vermeiden, die Druckluftsysteme verursachen können; der Behälter oder ein anmontiertes Teil dürfen nicht am Boden oder feststehenden Teilen (Pfeilern ...) befestigt werden; 6) Vorbeugung gegen Korrosion, bei neuen Betriebsbedingungen kann sich in Behälter Kondensat ansammeln, das täglich abgelassen werden muss. Dies kann entweder manuell durch Öffnen des Ablassventils oder durch eine automatische Kondensatkontrolle, falls diese an der Ausrüstung mit der richtigen Art der Ausrüstung verbunden ist, geschehen. Während der Wartung, alle 12 Monate, muss der Benutzer oder ein Kundendienst-Experte die Anwesenheit von Korrosion überprüfen und eine jährliche visuelle Kontrolle durchführen, wenn der Behälter mit einem Kompressor oder in der Gegenwart von Feuchtigkeit, oder in ungünstigen Bedingungen (geringer Durchzug, Luftfeuchtigkeit o.ä.) steht. Die Schichtdicke in geringeren Zonen des Behälters prüfen. Die tatsächliche Wandstärke des korrodierten Behälters darf auf keinen Fall (B) mm am Mantel und (C) mm an den Böden unterschreiten. Die tatsächliche Wandstärke des korrodierten Behälters darf auf keinen Fall (B) mm am Mantel und (C) mm an den Böden unterschreiten. 7) Agieren Sie ähnlich wie bei der Sicherheit, gemäß den geltenden Vorschriften. VERBODEN OP DE MANIPULATIE EN ONDOORZICHTIGE GEBRUIK VAN HET TOEGESTELDE. De gebruiker moet zich houden aan de wetgeving op het gebied van toestellen onder druk. Het gebruik van de druktoestellen is verboden.
	ISTRUZIONI D'USO L'attrezzatura a pressione è destinata all'accumulo d'aria compressa ed è calcolata per utilizzo principalmente statico. L'uso corretto dell'attrezzatura è premessa indispensabile per garantire la sicurezza. A tal scopo l'utente deve: 1) utilizzare correttamente l'attrezzatura nei limiti di pressione e di temperatura di progetto che sono riportati sulla targhetta del Costruttore e sulla dichiarazione di conformità che deve essere conservata con cura; 2) evitare di effettuare saldature sulle parti esperte a pressione; 3) utilizzare l'aria del serbatoio senza accoppiatori di sicurezza (accoppiatori di sicurezza e pressostati) e, se possibile, manometri efficaci e controllare in caso di necessità la loro sostituzione con altri di equivalenti caratteristiche, sentito in merito al Costruttore. In particolare, la sicurezza di deviazioni deve essere applicata direttamente sul recipiente senza possibilità di interruzione, deve avere una capacità di scarico superiore alla quantità di aria che può essere immessa nel recipiente, senza taratura superiore alla pressione di (A) bar. Sul manometro, l'ordine di pressione di (A) bar deve essere indicato con un segno rosso. 4) Evitare se possibile di utilizzare il serbatoio in locali non sufficientemente areati; evitare esponendolo a vibrazioni che il serbatoio in zone esposte a sorgenti di calore o nelle vicinanze di sostanze infiammabili; 5) evitare il serbatoio di vibrazioni in modo da evitare che il serbatoio durante l'esercizio sia soggetto a vibrazioni che possono generare per fatica, non bloccare o ancorare o a parti fisse (colonne...), il serbatoio o parti del suo sistema; 6) Prevenire la corrosione, in seconda delle condizioni d'impiego, si può accumulare all'interno del serbatoio della condensa che deve essere scaricata quotidianamente. Ciò può essere fatto manualmente aprendo il rubinetto di scarico attraverso lo scaricatore di condensa automatico o montando sul serbatoio l'effluente della manutenzione, annualmente l'utente o un esperto del servizio assistenza deve verificare l'assenza di eventuali corrosioni interne nel serbatoio ed effettuare un controllo visuale esterno. Se il recipiente è utilizzato con compressore d'aria o in ambienti che presentano un alto grado di umidità, o in condizioni di umidità (bassa ventilazione, agenti corrosivi...) le ispezioni dovrebbero essere effettuate più frequentemente. Lo spessore effettivo del recipiente dopo corrosione non dovrà essere inferiore a (B) mm per il mantello e (C) mm per i fondi; controllare regolarmente i rischi dovuti essere organizzata secondo la legge e il nome della Dava e l'istruttore è utilizzato. 7) Agire in quanto capo file per la protezione di maniera adeguata al caso previsto. ATTENZIONE: VIETATA LA MANIPOLAZIONE DEL SERBATOIO E OGNI UTILIZZAZIONE IMPROPRIA. Si raccomanda all'utente di attenersi a quanto richiesto dalla legge sull'uso degli apparecchi a pressione in vigore nei paesi di utilizzo. Il serbatoio con P > maggiore o pari a 3,00 bar per litro o pressione maggiore di 12 bar sono soggetti alle verifiche di primo impianto e alle visite periodiche da parte di enti preposti così come definito nel D.L. 379 del 01/12/2004.	ISTRUCTIONS FOR THE USE The device is not designed to be used for the accumulation of air compressed and is not designed to be subjected to rapid variations of pressure. The correct use of the device is a prerequisite for ensuring safety. To this end, the user must: 1) use the device correctly, within the pressure and temperature limits of design that are reported on the tag of the Constructor and in the declaration of conformity that must be kept with care; 2) avoid carrying out welding on the parts exposed to pressure; 3) use the air from the tank without safety couplings (safety couplings and pressure switches) and, if possible, effective manometers and check in case of necessity their replacement with others of equivalent characteristics, after consulting the Constructor. In particular, the safety of the device must be applied directly to the tank without the possibility of interruption, it must have a capacity of discharge superior to the quantity of air that can be introduced into the tank, without a rating higher than the pressure of (A) bar. On the manometer, the order of pressure of (A) bar must be indicated with a red mark; 4) avoid, if possible, to use the tank in non sufficiently ventilated rooms; avoid exposing the tank to vibrations that the tank in zones exposed to sources of heat or in the vicinity of inflammable substances; 5) avoid the tank of vibrations in order to avoid that the tank during its operation is subjected to vibrations that can generate fatigue, do not block or anchor or to parts fixed (columns...), the tank or parts of its system; 6) Prevent corrosion, according to the conditions of use, condensation may accumulate inside the tank, which must be discharged daily. This can be done manually by opening the drain tap through the automatic drain or by mounting on the tank the maintenance effluent, annually the user or an expert of the service assistance must verify the absence of possible corrosions inside the tank and carry out a visual external control. If the device is used with an air compressor or in environments that present a high degree of humidity, or in conditions of humidity (low ventilation, corrosive agents...) the inspections should be carried out more frequently. The effective thickness of the tank after corrosion must not be less than (B) mm for the shell and (C) mm for the bottom; regularly check the risks due to corrosion according to the law and the name of the Dava and the instructor is used; 7) act as the main person responsible for protection in a suitable manner as the case provides. WARNING: THE TANK IS NOT TO BE MANIPULATED AND ANY IMPROPER USE IS FORBIDDEN. It is recommended that the user complies with the legislation on the use of pressure equipment in force in the country of use. The tank with P > greater or equal to 3.00 bar per litre or pressure greater than 12 bar is subject to the checks of first installation and to the periodic checks by the competent bodies as defined in the D.L. 379 of 01/12/2004.
Page 2 di 2	MANIPOLAZIONE DELLA MANIPOLAZIONE DEL DISPOSITIVO Y TODA UTILIZACION IMPROPRIA. Se recomienda que el usuario del dispositivo se atenga a lo que se indica en la ley. (A) = 16 (B) = 4	

EXHIBIT ONLY - NOT USABLE

MINIMUM
HEADS
THICKNESS

MINIMUM
SHELL
THICKNESS
(CYLINDER
BODY)

DESIGN
PRESSURE

FITNESS DECLARATION

The vessels are not included in the range of applicability of the 2014/68/UE directive, because they are not equipped with any source of ignition. Upon request, can be supplied the Fitness Declaration Atex.



DICHIARAZIONE DI IDONEITÀ - DIRETTIVA 2014/34/UE
FITNESS DECLARATION - DIRECTIVE 2014/34/UE
(EN 45014:1999)

In riferimento a:

Art.1, par. 2, della direttiva 2014/34/UE, dtd. 26 febbraio 2014,
Capitoli 37 e 40 delle ATEX 2014/34/UE Guidelines 2nd Edition, dtd. Dicembre 2017
Sulla base dell'analisi dei rischi effettuata, l'attrezzatura: VEC01251 serbatoio 50lt 11bar

NON RIENTRA NEL CAMPO DI APPLICAZIONE DELLA DIRETTIVA 2014/34/UE

in quanto non possiede al suo interno ed al suo esterno nessuna sorgente di innesco propria.
Per questo motivo non è soggetta a nessuna valutazione e a nessuna marcatura come previsto dalla direttiva.


In accordance with:

Art.1, par. 2, of Directive 2014/34 / EU, dtd. 26 February 2014,
Chapters 37 and 40 of ATEX 2014/34/UE Guidelines 2nd Edition, dtd. December 2017
Based on the risk analysis carried out, the equipment: VE01251 Vessel 50lt 11bar

IS NOT INCLUDED IN THE RANGE OF APPLICABILITY OF THE 2014/34 /EU DIRECTIVE

because it does not has an own source of ignition.
For this reason, it is not subject to any evaluation or marking as required by the directive.

09/07/2020
Casalvolone (Novara)



-10°C AIR VESSELS



-10°C AIR VESSELS

SMALL SIZE VERTICAL
PAINTED - GALVANIZED


Material
Carbon steel

Fluid content
Compressed air / Nitrogen (group 2)

Finishing
RAL5015: External Ral 5015 blue paint (standard)
GALVANIZED: internal and external hot-dip galvanization

Upon request
1" couplings on heads

Directive 2014/29/UE
Operating pressure 11/16 bar
Operating temperature -10 +120°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	L	1	2	3	4	5	6	Weight
		lt	bar	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	kg

RAL 5015*

VEC01295	2014/29/UE	24	11	240	64	185	535	656	1/2"	=	1/2"	1/2"	=	3/8"	10
VEC01296	2014/29/UE	50	11	305	145	297	777	929	1/2"	1/2"	=	=	1/2"	3/8"	19
VEC00875	2014/29/UE	50	15	305	145	297	777	929	1/2"	1/2"	=	=	1/2"	3/8"	23

GALVANIZED

VEC02301	2014/29/UE	24	11	240	64	185	535	656	1"	=	1/2"	1/2"	=	3/8"	11
VEC01736	2014/29/UE	50	11	305	145	297	777	929	1"	1/2"	=	=	1/2"	3/8"	20

-10°C AIR VESSELS

SMALL SIZE HORIZONTAL
PAINTED - GALVANIZED


Material
Carbon steel

Fluid content
Compressed air / Nitrogen (group 2)

Finishing
RAL5015: External Ral 5015 blue paint (standard)
GALVANIZED: internal and external hot-dip galvanization

Upon request
1" couplings on heads

Directive 2014/29/UE
Operating pressure 11/16 bar
Operating temperature -10 +120°C



Horizontal vessels with fixed feet

CODE	Directive	Capacity	Operating pressure	De	A	B	C	D	E	H	a	b	c	x	y	j	z	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	kg

RAL 5015*

VEC01294	2014/29/UE	5	11	150	370	37,5	200	140	191	120	-	-	137,5	1/2"	-	-	1/4"	6,5
VEC01249	2014/29/UE	10	11	169	506	85	240	172	205	115	-	60	50	1/2"	-	3/8"	3/8"	8
VEC01237	2014/29/UE	15	11	196	522	85	240	172	205	135	-	60	50	1/2"	-	3/8"	3/8"	9
VEC01250	2014/29/UE	24	11	240	592	95	260	180	235	165	-	60	50	1/2"	-	3/8"	3/8"	10
VEC01251	2014/29/UE	50	11	305	784	100	400	236	285	203	60	60	60	1/2"	1/2"	1/2"	3/8"	19
VEC01715	2014/29/UE	24	16	240	592	95	260	180	235	165	-	60	50	1/2"	-	3/8"	3/8"	13
VEC02313	2014/29/UE	50	15	305	784	100	400	236	285	203	60	60	60	1/2"	1/2"	1/2"	3/8"	23

GALVANIZED

VEC03220	2014/29/UE	10	11	169	506	85	240	172	205	115	-	60	50	1"	-	3/8"	3/8"	8
VEC04702	2014/29/UE	15	11	196	522	85	240	172	205	135	-	60	50	1"	-	3/8"	3/8"	9
VEC03019	2014/29/UE	24	11	240	592	95	260	180	235	165	-	60	50	1"	-	3/8"	3/8"	10
VEC02779	2014/29/UE	50	11	305	784	100	400	236	285	203	60	60	60	1"	1/2"	1/2"	3/8"	19

-10°C AIR VESSELS

HORIZONTAL
PAINTED



Material
Carbon steel

Fluid content
Compressed air / Nitrogen (group 2)

Finishing
External Ral 5015 blue paint (standard)

Upon request
1" couplings on heads

Directive	2014/29/UE	2014/68/UE(PED)
Operating pressure	11/16 bar	12/16 bar
Operating temperature	-10 +120°C	-10 +50°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	E	F	H	a	b	c	x	y	k	j	z	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	kg

RAL 5015*

VEC01095	2014/29/UE	100	11	370	1016	550	125	352	306	258	45	80	45	2"	3/8"	1/2"	3/8"	3/8"	29
VEC02139	2014/29/UE	150	11	396	1240	650	175	368	322	271	50	130	50	2"	3/8"	1/2"	3/8"	3/8"	44
VEC01732	2014/29/UE	200	11	446	1364	750	175	440	385	288	50	150	50	2"	3/8"	1/2"	1/2"	3/8"	55
VEC01733	2014/29/UE	270	11	500	1458	800	175	455	402	315	50	130	50	2"	3/8"	1"	1/2"	3/8"	67
VEC00728	2014/29/UE	500	11	600	1858	1204	148	530	470	396	60	155	60	2"	3/8"	1"	1/2"	3/8"	130
VEC00873	2014/29/UE	720	11	750	1850	970	215	570	460	495	60	155	60	2"	3/8"	1"	1/2"	3/8"	178
VEC00707	2014/29/UE	900	11	800	1960	1014	243	605	490	500	60	155	60	2"	3/4"	1"	1/2"	1/2"	194
VEC00515	2014/68/UE(PED)	1000	12	800	2158	1014	343	605	490	500	100	155	60	2"	3/4"	1"	1/2"	1/2"	210
VEC00739	2014/68/UE(PED)	1500	12	1000	2135	900	300	691	575	608	200	200	-	2"	1/2"	1/2"	-	1/2"	325
VEC00680	2014/68/UE(PED)	2000	12	1100	2252	1100	275	800	685	652	200	215	-	2"	1/2"	1/2"	-	1/2"	394
VEC00534	2014/68/UE(PED)	3000	12	1200	2850	1265	227	820	710	698	1230	200	-	2"	1/2"	1/2"	-	1/2"	605
VEC02257	2014/29/UE	270	16	500	1484	800	175	455	402	315	50	130	50	2"	3/8"	1"	1/2"	3/8"	104
VEC01113	2014/29/UE	500	16	600	1858	1204	148	530	470	396	60	155	60	2"	3/8"	1"	1/2"	3/8"	163
VEC00520	2014/68/UE(PED)	1000	16	800	2158	1014	343	605	490	500	100	155	60	2"	3/4"	1"	1/2"	1/2"	253
VEC00531	2014/68/UE(PED)	2000	16	1000	2570	1350	300	691	575	608	220	300	-	2"	1/2"	1/2"	-	1/2"	395
VEC02912	2014/68/UE(PED)	3000	16	1200	2850	1265	227	820	710	698	1230	200	-	2"	1/2"	1/2"	-	1/2"	640

-10°C AIR VESSELS

HORIZONTAL
GALVANIZED - ALM


Material
Carbon steel

Fluid content
Compressed air / Nitrogen (group 2)

Finishing
GALVANIZED: internal and external hot-dip galvanization
ALM: External Ral 5015 blue paint (standard) and Internal Ral 5005 ALM paint

Upon request
1" couplings on heads

Directive	2014/29/UE	2014/68/UE(PED)
Operating pressure	11/16 bar	12/16 bar
Operating temperature	-10 +120°C	-10 +50°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	E	F	H	a	b	c	x	y	k	j	z	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	kg

GALVANIZED

VEC01735	2014/29/UE	270	11	500	1458	800	175	455	402	315	50	130	50	2"	3/8"	1"	1/2"	3/8"	70
VEC00874	2014/29/UE	500	11	600	1858	1204	148	530	470	396	60	155	60	2"	3/8"	1"	1/2"	3/8"	134
VEC02069	2014/29/UE	720	11	750	1850	970	215	570	460	495	60	155	60	2"	3/8"	1"	1/2"	3/8"	181
VEC02277	2014/68/UE(PED)	1000	12	800	2158	1014	343	605	490	500	100	155	60	2"	3/4"	1"	1/2"	1/2"	215
VEC00690	2014/68/UE(PED)	2000	12	1100	2252	1100	275	800	685	652	200	215	-	2"	1/2"	1/2"	-	1/2"	398
VEC02202	2014/68/UE(PED)	3000	12	1200	2850	1265	227	820	710	698	1230	200	-	2"	1/2"	1/2"	-	1/2"	609

ALM

VEC02317	2014/29/UE	270	11	500	1458	800	175	455	402	315	50	130	50	2"	3/8"	1"	1/2"	3/8"	67
VEC02127	2014/29/UE	500	11	600	1858	1204	148	530	470	396	60	155	60	2"	3/8"	1"	1/2"	3/8"	130
VEC02286	2014/29/UE	720	11	750	1850	970	215	570	460	495	60	155	60	2"	3/8"	1"	1/2"	3/8"	178
VEC02285	2014/68/UE(PED)	1000	12	800	2158	1014	343	605	490	500	100	155	60	2"	3/4"	1"	1/2"	1/2"	210
VEC02100	2014/68/UE(PED)	2000	12	1100	2252	1100	275	800	685	652	200	215	-	2"	1/2"	1/2"	-	1/2"	394
VEC02284	2014/68/UE(PED)	3000	12	1200	2850	1265	227	820	710	698	1230	200	-	2"	1/2"	1/2"	-	1/2"	605

-10°C AIR VESSELS

HORIZONTAL WITH PLATE
PAINTED - GALVANIZED

Material
Carbon steel



Fluid content
Compressed air / Nitrogen (group 2)

Finishing
RAL5015: External Ral 5015 blue paint (standard) Galvanized : internal and external hot-dip galvanization

Directive 2014/29/UE

Operating pressure 11 bar

Operating temperature -10 +120°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	E	F	H	a	b	c	x	y	k	j	z	Plate dimensions	Weight	
		lt	bar	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	mm	mm	kg

RAL 5015*

VEC04713	2014/29/UE	50	11	305	784	100	400	239	285	203	60	60	60	1/2"	1/2"	-	1/2"	3/8"	220	400	24
VEC04711	2014/29/UE	100	11	370	1016	550	125	352	306	258	45	80	45	1/2"	3/8"	1/2"	3/8"	3/8"	220	400	34
VEC04709	2014/29/UE	200	11	446	1364	750	175	440	385	288	50	130	50	1/2"	3/8"	1/2"	1/2"	3/8"	240	800	65
VEC04707	2014/29/UE	270	11	500	1458	800	175	456	402	315	50	130	50	1/2"	3/8"	1"	1/2"	3/8"	240	800	77
VEC04705	2014/29/UE	500	11	600	1858	1205	148	530	470	396	60	155	60	2"	3/8"	1"	1/2"	3/8"	300	800	143

GALVANIZED

VEC04714	2014/29/UE	50	11	305	784	100	400	239	285	203	60	60	60	1"	1/2"	-	1/2"	3/8"	220	400	25
VEC04712	2014/29/UE	100	11	370	1016	550	125	352	306	258	45	80	45	2"	3/8"	1/2"	3/8"	3/8"	220	400	38
VEC04710	2014/29/UE	200	11	446	1364	750	175	440	385	288	50	130	50	2"	3/8"	1/2"	1/2"	3/8"	240	800	70
VEC04708	2014/29/UE	270	11	500	1458	800	175	456	402	315	50	130	50	2"	3/8"	1"	1/2"	3/8"	240	800	81
VEC04706	2014/29/UE	500	11	600	1858	1205	148	530	470	396	60	155	60	2"	3/8"	1"	1/2"	3/8"	300	800	149

-10°C AIR VESSELS

VERTICAL
PAINTED 11 · 12 · 16 bar

Material
Carbon steel



Fluid content
Compressed air / Nitrogen (group 2)

Finishing
External Ral 5015 blue paint (standard)

Directive 2014/29/UE 2014/68/UE(PED)

Operating pressure 11/16 bar 12/16 bar

Operating temperature -10 +120°C -10 +50°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	D	L	1	2	3	4	5	6	7	8	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	inch	inch	kg

RAL 5015*

VEC00644	2014/29/UE	100	11	370	180	355	1055	=	1213	1 1/2"	3/4"	=	3/8"	3/8"	=	3/4"	=	31
VEC00709	2014/29/UE	150	11	396	170	385	1210	=	1430	1 1/2"	1"	=	3/8"	3/8"	=	1"	=	44
VEC00645	2014/29/UE	200	11	446	175	400	1225	=	1557	1 1/2"	1"	=	3/8"	3/8"	=	1"	=	55
VEC00478	2014/29/UE	270	11	500	175	599	1304	=	1648	1 1/2"	1"	1"	=	3/8"	1"	=	=	67
VEC00493	2014/29/UE	500	11	600	155	785	1665	=	2050	1 1/2"	1"	1"	=	3/8"	1"	1"	=	115
VEC00370	2014/29/UE	500	11	600	155	785	1665	=	2050	2"	2"	2"	=	3/8"	2"	2"	=	116
VEC00510	2014/29/UE	720	11	750	147	880	1705	=	2030	2"	2"	2"	3/8"	3/8"	2"	2"	=	178
VEC06236	2014/29/UE	720	11	800	145	580	1310	=	1745	2"	2"	2"	3/8"	3/8"	2"	2"	=	155
VEC05025	2014/29/UE	900	11	800	145	875	1805	=	2140	2"	2"	2"	3/8"	3/8"	2"	2"	=	194
VEC00518	2014/68/UE(PED)	1000	12	800	145	770	1720	=	2350	2"	2"	2"	3/8"	3/8"	2"	2"	=	210
VEC00525	2014/68/UE(PED)	1500	12	1000	170	680	1780	=	2305	2"	2"	2"	1/2"	1/2"	2"	2"	=	320
VEC00528	2014/68/UE(PED)	2000	12	1100	200	770	1970	=	2490	2"	2"	2"	1/2"	1/2"	2"	2"	=	388
VEC00530	2014/68/UE(PED)	2000	12	1100	200	770	1970	=	2490	2"	3"	3"	1/2"	1/2"	3"	3"	=	390
VEC00535	2014/68/UE(PED)	3000	12	1200	140	830	2250	1540	2990	2"	2"	2"	1/2"	1/2"	2"	2"	2"	594
VEC01360	2014/68/UE(PED)	3000	12	1200	140	830	2250	1540	2990	2"	3"	3"	1/2"	1/2"	3"	3"	3"	596
VEC00879	2014/29/UE	270	16	500	175	599	1304	=	1648	1 1/2"	1"	1"	=	3/8"	1"	=	=	101
VEC00139	2014/29/UE	500	16	600	155	785	1665	=	2050	2"	2"	2"	=	3/8"	2"	2"	=	145
VEC00366	2014/68/UE(PED)	1000	16	800	145	770	1720	=	2350	2"	2"	2"	3/8"	3/8"	2"	2"	=	245
VEC01058	2014/68/UE(PED)	1500	16	1000	170	680	1780	=	2305	2"	2"	2"	1/2"	1/2"	2"	2"	=	423
VEC00532	2014/68/UE(PED)	2000	16	1000	170	770	2185	=	2740	2"	2"	2"	1/2"	1/2"	2"	2"	=	450
VEC00537	2014/68/UE(PED)	3000	16	1200	140	830	2250	1540	2990	2"	2"	2"	1/2"	1/2"	2"	2"	2"	630

-10°C AIR VESSELS



VERTICAL
GALVANIZED

11 · 12 · 16 bar

Material
Carbon steel suitable for galvanization

Fluid content
Compressed air / Nitrogen (group 2)

Finishing
Internal and external hot-dip galvanization



Directive	2014/29/UE	2014/68/UE(PED)
Operating pressure	11/16 bar	12/16 bar
Operating temperature	-10 +120°C	-10 +50°C

CODE	Directive	Capacity lt	Operating pressure bar	De mm	A mm	B mm	C mm	D mm	L mm	1 inch	2 inch	3 inch	4 inch	5 inch	6 inch	7 inch	8 inch	Weight kg
------	-----------	----------------	------------------------------	----------	---------	---------	---------	---------	---------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	--------------

GALVANIZED

VEC00901	2014/29/UE	100	11	370	170	355	1055	=	1213	2"	3/4"	=	3/8"	3/8"	=	3/4"	=	32
VEC02471	2014/29/UE	150	11	396	170	385	1210	=	1430	2"	1"	=	3/8"	3/8"	=	1"	=	46
VEC00908	2014/29/UE	200	11	446	170	400	1225	=	1557	2"	1"	=	3/8"	3/8"	=	1"	=	57
VEC00909	2014/29/UE	270	11	500	170	599	1304	=	1648	2"	1"	1"	=	3/8"	1"	=	=	70
VEC00906	2014/29/UE	500	11	600	155	785	1665	=	2050	2"	2"	2"	=	3/8"	2"	2"	=	119
VEC00907	2014/29/UE	720	11	750	135	880	1705	=	2030	2"	2"	2"	3/8"	3/8"	2"	2"	=	181
VEC05980	2014/29/UE	720	11	800	145	580	1310	=	1745	2"	2"	2"	3/8"	3/8"	2"	2"	=	155
VEC04703	2014/29/UE	900	11	800	145	875	1805	=	2140	2"	2"	2"	3/8"	3/8"	2"	2"	=	198
VEC00519	2014/68/UE(PED)	1000	12	800	145	770	1720	=	2350	2"	2"	2"	2"	3/8"	3/8"	2"	=	214
VEC00526	2014/68/UE(PED)	1500	12	1000	170	680	1780	=	2305	2"	2"	2"	2"	1/2"	1/2"	2"	=	325
VEC00529	2014/68/UE(PED)	2000	12	1100	200	770	1970	=	2490	2"	2"	2"	2"	1/2"	1/2"	2"	=	394
VEC02276	2014/68/UE(PED)	2000	12	1100	200	770	1970	=	2490	2"	3"	3"	1/2"	1/2"	3"	3"	=	398
VEC00536	2014/68/UE(PED)	3000	12	1200	140	830	2250	1540	2990	2"	2"	2"	2"	1/2"	1/2"	2"	2"	600
VEC01368	2014/68/UE(PED)	3000	12	1200	140	830	2250	1540	2990	2"	3"	3"	1/2"	1/2"	3"	3"	3"	604
VEC00900	2014/29/UE	270	16	500	170	599	1304	=	1648	2"	1"	1"	=	3/8"	1"	=	=	104
VEC00500	2014/29/UE	500	16	600	155	785	1665	=	2050	2"	2"	2"	=	3/8"	2"	2"	=	149
VEC00402	2014/68/UE(PED)	1000	16	800	150	770	1720	=	2350	2"	2"	2"	3/8"	3/8"	2"	2"	=	249
VEC02278	2014/68/UE(PED)	1500	16	1000	170	680	1780	=	2305	2"	2"	2"	1/2"	1/2"	2"	2"	=	428
VEC00533	2014/68/UE(PED)	2000	16	1000	170	770	2185	=	2740	2"	2"	2"	1/2"	1/2"	2"	2"	=	455
VEC00538	2014/68/UE(PED)	3000	16	1200	140	830	2250	1540	2990	2"	2"	2"	1/2"	1/2"	2"	2"	2"	635

-10°C AIR VESSELS




VERTICAL
ALM

11 · 12 · 16 bar

Material
Carbon steel suitable for galvanization

Fluid content
Compressed air / Nitrogen (group 2)

Finishing
External Ral 5015 blue paint (standard)
Internal Ral 5005 ALM paint



ALM
RAL 5005
CARBON
STEEL
RAL 5015

Directive	2014/29/UE	2014/68/UE(PED)
Operating pressure	11/16 bar	12/16 bar
Operating temperature	-10 +120°C	-10 +50°C

CODE	Directive	Capacity lt	Operating pressure bar	De mm	A mm	B mm	C mm	D mm	L mm	1 inch	2 inch	3 inch	4 inch	5 inch	6 inch	7 inch	8 inch	Weight kg
------	-----------	----------------	------------------------------	----------	---------	---------	---------	---------	---------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	--------------

ALM


VEC01125	2014/29/UE	270	11	500	170	599	1304	=	1648	2"	1"	1"	=	3/8"	1"	=	=	67
VEC01118	2014/29/UE	500	11	600	155	785	1665	=	2050	2"	2"	2"	=	3/8"	2"	2"	=	116
VEC01119	2014/29/UE	720	11	800	145	580	1310	=	1745	2"	2"	2"	3/8"	3/8"	2"	2"	=	155
VEC01120	2014/29/UE	900	11	800	145	875	1805	=	2140	2"	1 1/2"	1 1/2"	3/8"	3/8"	1 1/2"	1 1/2"	=	194
VEC01116	2014/68/UE(PED)	1000	12	800	145	770	1720	=	2350	2"	2"	2"	3/8"	3/8"	2"	2"	=	210
VEC01121	2014/68/UE(PED)	1500	12	1000	170	680	1780	=	2305	2"	2"	2"	1/2"	1/2"	2"	2"	=	320
VEC01122	2014/68/UE(PED)	2000	12	1100	200	770	1970	=	2490	2"	2"	2"	1/2"	1/2"	2"	2"	=	388
VEC01123	2014/68/UE(PED)	3000	12	1200	140	830	2250	1540	2990	2"	2"	2"	1/2"	1/2"	2"	2"	2"	594
VEC01935	2014/29/UE	270	16	500	175	599	1304	=	1648	1/2"	1"	1"	=	3/8"	1"	=	=	101
VEC02279	2014/29/UE	500	16	600	155	785	1665	=	2050	2"	2"	2"	=	3/8"	2"	2"	=	145
VEC02310	2014/68/UE(PED)	1000	16	800	145	770	1720	=	2350	2"	2"	2"	3/8"	3/8"	2"	2"	=	245
VEC02143	2014/68/UE(PED)	2000	16	1000	170	770	2185	=	2740	2"	2"	2"	1/2"	1/2"	2"	2"	=	450
VEC02464	2014/68/UE(PED)	3000	16	1200	140	830	2250	1540	2990	2"	2"	2"	1/2"	1/2"	2"	2"	2"	630

-10°C AIR VESSELS


VERTICAL VACUUM
PAINTED

- Material**
Carbon steel
- Fluid content**
Compressed air / Nitrogen (group 2)
- Finishing**
External Ral 5015 blue paint (standard)
- Upon request**
Horizontal version

- Directive**
- Operating pressure**
-1 bar
- Operating temperature**
-10 +120°C



A vacuum system is required in certain industrial process operations in order to prevent chemical or physical processes caused by the action of atmospheric gases.



The vessels are used to reproduce a setting where gas pressure is lower than the atmospheric one. Vacuum vessels are not governed by any Directive and are therefore excluded from CE marking requirements.

All vessels are supplied with name plate bearing Manufacturer's name, operating temperature, operating pressure and product's serial number.

CODE	Directive	Capacity	Operating pressure	De	A	B	C	D	L	1	2	3	4	5	6	7-8	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	inch	kg

RAL 5015*


VAC00041	=====	100	-1	370	180	355	1055	=	1213	2"	3/4"	=	3/8"	3/8"	=	3/4	40
VAC00012	=====	270	-1	500	170	599	1304	=	1648	2"	1"	1"	=	3/8"	1"	=	101
VAC00005	=====	500	-1	600	155	785	1665	=	2050	2"	2"	2"	=	3/8"	2"	2"	145
VAC00004	=====	1000	-1	800	145	760	1700	=	2350	2"	2"	2"	3/8"	3/8"	2"	2"	245
VAC00006	=====	2000	-1	1100	200	770	1970	=	2490	2"	2"	2"	1/2"	1/2"	2"	2"	450
VAC00013	=====	3000	-1	1200	140	830	2250	1540	2990	2"	2"	2"	1/2"	1/2"	2"	2"	630

-10°C AIR VESSELS

VERTICAL AUTOCLAVE
GALVANIZED

- Material**
Carbon steel suitable for galvanization
- Fluid content**
Compressed air / Water (group 2)
- Finishing**
Internal and external hot-dip galvanization
- Upon request**
Horizontal version

- Directive**
- Operating pressure**
8 bar
- Operating temperature**
-10 +50°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	D	E	H	1	2-3-4	5-6-7	8	9	10	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	kg

GALVANIZED

VEC01254	2014/68/UE(PED)	100	8	370	85	345	515	615	815	1145	2"	1"	1/2"	1"1/4	1/2"	2"	34
VEC01256	2014/68/UE(PED)	200	8	446	80	360	684	784	1184	1488	2"	1"	1/2"	1"1/4	1/2"	2"	57
VEC01257	2014/68/UE(PED)	200	8	500	80	360	669	769	1160	1461	2"	1"	1/2"	1"1/4	1/2"	2"	59
VEC01259	2014/68/UE(PED)	300	8	500	130	425	856	956	1356	1782	2"	1"1/4	1/2"	1"1/4	1/2"	2"	73
VEC01260	2014/68/UE(PED)	300	8	550	130	432	732	832	1225	1530	2"	1"1/4	1/2"	1"1/4	1/2"	2"	73
VEC01261	2014/68/UE(PED)	500	8	600	120	440	944	1044	1594	1968	2"	1"1/2	1/2"	1"1/4	1/2"	2"	106
VEC01262	2014/68/UE(PED)	500	8	650	120	440	840	940	1490	1802	2"	1"1/2	1/2"	1"1/4	1/2"	2"	94
VEC01264	2014/68/UE(PED)	750	8	750	100	500	950	1050	1700	1984	2"	2"	1/2"	1"1/4	1/2"	2"	125
VEC01265	2014/68/UE(PED)	750	8	800	110	465	865	965	1430	1820	2"	2"	1/2"	1"1/4	1/2"	2"	127
VEC01266	2014/68/UE(PED)	1000	8	800	115	525	1025	1125	1875	2319	2"	2"	1/2"	1"1/4	1/2"	2"	189

-20°C AIR VESSELS



-20°C AIR VESSELS

VERTICAL
PAINTED

11 · 12 · 16 bar

Material

Carbon steel

Fluid content

Compressed air / Nitrogen / Argon / Helium
/ Oil / Oxygen (group 1 hydrogen excluded)

Finishing

External Ral 5015 blue paint (standard)

Upon request

Inspection ports
100x150 mm handhole (from 1000 to 3000 lt)
Flanged connections
Horizontal version

Directive

2014/68/UE(PED) 2014/68/UE(PED)

Operating pressure


11/16 bar

12/16 bar

Operating temperature

* -20 +50°C

-20 +80°C



CODE	Directive	Capacity lt	Operating pressure bar	De mm	A mm	B mm	C mm	L mm	1 inch	2 inch	3 inch	4 inch	5 inch	6 inch	7 inch	Weight kg
------	-----------	----------------	------------------------------	----------	---------	---------	---------	---------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	--------------

RAL 5015*

VEC02287	2014/68/UE(PED)	*500	11	600	155	785	1665	2050	2"	2"	2"	=	3/8"	2"	2"	116
VEC01656	2014/68/UE(PED)	1000	12	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	210
VEC01987	2014/68/UE(PED)	1500	12	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	320
VEC01657	2014/68/UE(PED)	2000	12	1100	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"	388
VEC01658	2014/68/UE(PED)	3000	12	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	594
VEC02289	2014/68/UE(PED)	*500	16	600	155	785	1665	2050	2"	2"	2"	=	3/8"	2"	2"	145
VEC01918	2014/68/UE(PED)	1000	16	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	245
VEC02290	2014/68/UE(PED)	1500	16	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	423
VEC02288	2014/68/UE(PED)	2000	16	1000	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"	450
VEC02051	2014/68/UE(PED)	3000	16	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	630

VERTICAL
GALVANIZED - ALM 11 · 12 · 16 bar


Material
Carbon steel

Fluid content
Compressed air / Nitrogen / Argon / Helium
/ Oil / Oxygen (group 1 hydrogen excluded)

Finishing
GALVANIZED: internal and external
hot-dip galvanization
ALM: External Ral 5015 blue paint (standard)
and Internal Ral 5005 ALM paint

Upon request
Inspection ports
100x150 mm handhole (from 1000 to 3000 lt)
Flanged connections
Horizontal version

Directive	2014/68/UE(PED)	2014/68/UE(PED)
Operating pressure	11 bar	12 bar
Operating temperature	* -20 +50°C	-20 +80°C



CODE	Directive	Capacity lt	Operating pressure bar	De mm	A mm	B mm	C mm	L mm	1 inch	2 inch	3 inch	4 inch	5 inch	6 inch	7 inch	Weight kg
------	-----------	----------------	------------------------------	----------	---------	---------	---------	---------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	--------------

GALVANIZED

VEC02291	2014/68/UE(PED)	*500	11	600	155	785	1665	2050	2"	2"	2"	=	3/8"	2"	2"	119
VEC02292	2014/68/UE(PED)	1000	12	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	214
VEC02293	2014/68/UE(PED)	1500	12	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	325
VEC02294	2014/68/UE(PED)	2000	12	1100	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"	394
VEC02295	2014/68/UE(PED)	3000	12	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	600
VEC02296	2014/68/UE(PED)	*500	16	600	155	785	1665	2050	2"	2"	2"	=	3/8"	2"	2"	149
VEC02297	2014/68/UE(PED)	1000	16	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	249
VEC02298	2014/68/UE(PED)	1500	16	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	428
VEC02299	2014/68/UE(PED)	2000	16	1000	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"	455
VEC02300	2014/68/UE(PED)	3000	16	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	635

ALM

VEC02302	2014/68/UE(PED)	*500	11	600	155	785	1665	2050	2"	2"	2"	=	3/8"	2"	2"	116
VEC02303	2014/68/UE(PED)	1000	12	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	210
VEC02304	2014/68/UE(PED)	1500	12	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	320
VEC02305	2014/68/UE(PED)	2000	12	1100	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"	388
VEC02306	2014/68/UE(PED)	3000	12	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	594
VEC02307	2014/68/UE(PED)	*500	16	600	155	785	1665	2050	2"	2"	2"	=	3/8"	2"	2"	145
VEC02074	2014/68/UE(PED)	1000	16	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	245
VEC02308	2014/68/UE(PED)	1500	16	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	423
VEC02309	2014/68/UE(PED)	2000	16	1000	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"	450
VEC02247	2014/68/UE(PED)	3000	16	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	630

VERTICAL FOR OXYGEN
PAINTED


Material
Carbon steel

Fluid content
Oxygen (group 1 hydrogen excluded)

Finishing
External Ral 9010 white paint
Internal Ral 5005 ALM paint

Upon request
Inspection ports
100x150 mm handhole
300x400 mm manhole
Flanged connections
Versione orizzontale

Directive	2014/68/UE(PED)	2014/68/UE(PED)
Operating pressure	11 bar	12 bar
Operating temperature	* -20 +50°C	-20 +80°C



CODE	Directive	Capacity lt	Operating pressure bar	De mm	A mm	B mm	C mm	L mm	1 inch	2 inch	3 inch	4 inch	5 inch	6 inch	7 inch	Weight kg
------	-----------	----------------	------------------------------	----------	---------	---------	---------	---------	-----------	-----------	-----------	-----------	-----------	-----------	-----------	--------------



RAL9010+ALM

VEC02176	2014/68/UE(PED)	* 500	11	600	155	785	1665	2050	2"	2"	2"	=	3/8"	2"	2"	116
VEC03412	2014/68/UE(PED)	800	12	800	145	875	1605	1940	2"	2"	2"	3/8"	3/8"	2"	2"	180
VEC01719	2014/68/UE(PED)	1000	12	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	210
VEC01720	2014/68/UE(PED)	1500	12	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	320
VEC01721	2014/68/UE(PED)	2000	12	1100	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"	388
VEC01722	2014/68/UE(PED)	3000	12	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	594
VEC01723	2014/68/UE(PED)	4000	12	1450	225	800	2145	2790	2"	3"	3"	3/4"	3/8"	=	3"	835
VEC01724	2014/68/UE(PED)	5000	12	1450	225	800	2745	3390	2"	3"	3"	3/4"	3/8"	=	3"	962

VERTICAL OVERSIZE
PAINTED

- Material**
Carbon steel
- Fluid content**
Compressed air / Nitrogen / Argon / Helium
/ Oil / Oxygen (group 1 hydrogen excluded)
- Finishing**
External Ral 5015 blue paint (standard)
- Upon request**
Inspection ports
100x150 mm handhole
300x400 mm manhole
Flanged connections

Directive 2014/68/UE(PED)
Operating pressure 8/12/16 bar
Operating temperature -20 +80°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	D	E	F	L	1	2-3-4-5	6-7-8-9	10	11	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	kg

RAL 5015*

VEC02311	2014/68/UE(PED)	5000	8	1650	175	1150	2200	=	=	1950	3200	2"	3"	=	3/4"	3/8"	1120
VEC02280	2014/68/UE(PED)	8000	8	1650	175	1150	1930	2460	3310	1680	4315	2"	3"	3"	3/4"	3/8"	1400
VEC02312	2014/68/UE(PED)	10000	8	1650	175	1150	2200	3150	4250	1950	5200	2"	3"	3"	3/4"	3/8"	1730
VEC01297	2014/68/UE(PED)	4000	12	1450	225	800	2145	=	=	=	2790	2"	3"	=	3/4"	3/8"	835
VEC01298	2014/68/UE(PED)	5000	12	1450	225	800	2745	=	=	=	3390	2"	3"	=	3/4"	3/8"	962
VEC00755	2014/68/UE(PED)	5000	12	1650	175	1150	2200	=	=	1950	3200	2"	3"	=	3/4"	3/8"	1360
VEC01299	2014/68/UE(PED)	6000	12	1450	225	800	3345	=	=	=	3990	2"	3"	=	3/4"	3/8"	1090
VEC01300	2014/68/UE(PED)	8000	12	1650	175	1150	1930	2460	3310	1680	4315	2"	3"	3"	3/4"	3/8"	1730
VEC00815	2014/68/UE(PED)	10000	12	1650	175	1150	2200	3150	4250	1950	5200	2"	3"	3"	3/4"	3/8"	2015
VEC02666	2014/68/UE(PED)	4000	16	1450	225	800	2145	=	=	=	2790	2"	3"	=	3/4"	3/8"	995
VEC02667	2014/68/UE(PED)	5000	16	1450	225	800	2745	=	=	=	3390	2"	3"	=	3/4"	3/8"	1145
VEC02668	2014/68/UE(PED)	6000	16	1450	225	800	3345	=	=	=	3990	2"	3"	=	3/4"	3/8"	1295
VEC01899	2014/68/UE(PED)	10000	16	1650	175	1150	2200	3150	4250	1950	5200	2"	3"	3"	3/4"	3/8"	2585

VERTICAL OVERSIZE
GALVANIZED - ALM

- Material**
Carbon steel
- Fluid content**
Compressed air / Nitrogen / Argon / Helium
/ Oil / Oxygen (group 1 hydrogen excluded)
- Finishing**
Internal and external hot-dip galvanization
Internal Ral 5005 ALM paint
- Upon request**
Inspection ports
100x150 mm handhole
300x400 mm manhole
Flanged connections

Directive 2014/68/UE(PED)
Operating pressure 8/12/16 bar
Operating temperature -20 +80°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	D	E	F	L	1	2-3-4-5	6-7-8-9	10	11	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	kg

GALVANIZED

VEC02281	2014/68/UE(PED)	5000	8	1650	175	1150	2200	=	=	1950	3200	2"	3"	=	3/4"	3/8"	1120
VEC02282	2014/68/UE(PED)	8000	8	1650	175	1150	1930	2460	3310	1680	4315	2"	3"	3"	3/4"	3/8"	1400
VEC02283	2014/68/UE(PED)	10000	8	1650	175	1150	2200	3150	4250	1950	5200	2"	3"	3"	3/4"	3/8"	1730
VEC01725	2014/68/UE(PED)	4000	12	1450	225	800	2145	=	=	=	2790	2"	3"	=	3/4"	3/8"	835
VEC01726	2014/68/UE(PED)	5000	12	1450	225	800	2745	=	=	=	3390	2"	3"	=	3/4"	3/8"	962
VEC00856	2014/68/UE(PED)	5000	12	1650	175	1150	2200	=	=	1950	3200	2"	3"	=	3/4"	3/8"	1360
VEC01395	2014/68/UE(PED)	6000	12	1450	225	800	3345	=	=	=	3990	2"	3"	=	3/4"	3/8"	1090
VEC01727	2014/68/UE(PED)	8000	12	1650	175	1150	1930	2460	3310	1680	4315	2"	3"	3"	3/4"	3/8"	1730
VEC00982	2014/68/UE(PED)	10000	12	1650	175	1150	2200	3150	4250	1950	5200	2"	3"	3"	3/4"	3/8"	2016
VEC01728	2014/68/UE(PED)	4000	16	1450	225	800	2145	=	=	=	2790	2"	3"	=	3/4"	3/8"	995
VEC01729	2014/68/UE(PED)	5000	16	1450	225	800	2745	=	=	=	3390	2"	3"	=	3/4"	3/8"	1145
VEC01730	2014/68/UE(PED)	6000	16	1450	225	800	3345	=	=	=	3990	2"	3"	=	3/4"	3/8"	1295
VEC02467	2014/68/UE(PED)	10000	16	1650	175	1150	2200	3150	4250	1950	5200	2"	3"	3"	3/4"	3/8"	2585

ALM

VEC01614	2014/68/UE(PED)	4000	12	1450	225	800	2145	=	=	=	2790	2"	3"	=	3/4"	3/8"	835
VEC01344	2014/68/UE(PED)	5000	12	1450	225	800	2745	=	=	=	3390	2"	3"	=	3/4"	3/8"	962
VEC01124	2014/68/UE(PED)	5000	12	1650	175	1150	2200	=	=	1950	3200	2"	3"	=	3/4"	3/8"	1360
VEC04723	2014/68/UE(PED)	10000	12	1650	175	1150	2200	3150	4250	1950	5200	2"	3"	3"	3/4"	3/8"	2016
VEC02465	2014/68/UE(PED)	4000	16	1450	225	800	2145	=	=	=	2790	2"	3"	=	3/4"	3/8"	995
VEC02466	2014/68/UE(PED)	5000	16	1450	225	800	2745	=	=	=	3390	2"	3"	=	3/4"	3/8"	1145

HORIZONTAL OVERSIZE
PAINTED - GALVANIZED - ALM



Material
Carbon steel

Fluid content
Compressed air / Nitrogen / Argon / Helium
/ Oil / Oxygen (group 1 hydrogen excluded)

Finishing
RAL 5015: External Ral 5015 blue paint
(standard)
GALVANIZED: internal and external
hot-dip galvanization
ALM: External Ral 5015 blue paint (standard)
and Internal Ral 5005 ALM paint

Upon request
Inspection ports
100x150 mm handhole
300x400 mm manhole - Flanged connections

Directive 2014/68/UE(PED)
Operating pressure 12 bar
Operating temperature -20 +80°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	F	H	a	b	x	y	k	j	z	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	kg

RAL 5015*

VEC06212	2014/68/UE(PED)	4000	12	1450	2560	1700	300	1267	937	222	300	2"	3/4"	3/8"	3"	1/2"	890
VEC02410	2014/68/UE(PED)	5000	12	1450	3184	1700	300	1267	937	222	300	2"	3/4"	3/8"	3"	1/2"	1060
VEC00772	2014/68/UE(PED)	5000	12	1650	2962	1300	350	1267	1035	300	450	2"	3/4"	3/8"	3"	1/2"	1380
VEC02323	2014/68/UE(PED)	10000	12	1650	4912	2080	1000	1267	1035	450	300	2"	3/4"	3/8"	3"	2"	2240

GALVANIZED

VEC03850	2014/68/UE(PED)	4000	12	1450	2560	1700	300	1267	937	222	300	2"	3/4"	3/8"	3"	1/2"	930
VEC04698	2014/68/UE(PED)	5000	12	1450	3184	1700	300	1267	937	222	300	2"	3/4"	3/8"	3"	1/2"	1100
VEC04699	2014/68/UE(PED)	5000	12	1650	2962	1300	350	1267	1035	300	450	2"	3/4"	3/8"	3"	1/2"	1410
VEC04701	2014/68/UE(PED)	10000	12	1650	4912	2080	1000	1267	1035	450	300	2"	3/4"	3/8"	3"	2"	2320

ALM

VEC02833	2014/68/UE(PED)	5000	12	1450	3184	1700	300	1267	937	222	300	2"	3/4"	3/8"	3"	1/2"	1060
VEC04700	2014/68/UE(PED)	5000	12	1650	2962	1300	350	1267	1035	300	450	2"	3/4"	3/8"	3"	1/2"	1380

FLANGED CONNECTIONS
AND NON-MANDATORY
INSPECTION OPENINGS

The following table is valid only for vessels with operating temperature not less than -20°C and pressure of 11 and 16 bar (from page 25 to page 30)



Volume	Pressure	DN40	DN50	DN65	DN80	DN90	DN100	DN125	DN150	DN200	DN250	Handhole	Manhole
	bar											100x150 mm	300x400 mm

1000	12	•	•	•	•	•	•	•	•	•	•	•	•
1000	16	•	•	•	•	•	•	•	•	•	•	•	•
1500	12	•	•	•	•	•	•	•	•	•	•	•	•
1500	16	•	•	•	•	•	•	•	•	•	•	•	•
2000	12	•	•	•	•	•	•	•	•	•	•	•	•
2000	16	•	•	•	•	•	•	•	•	•	•	•	•
3000	12	•	•	•	•	•	•	•	•	•	•	•	•
3000	16	•	•	•	•	•	•	•	•	•	•	•	•
4000	12	•	•	•	•	•	•	•	•	•	•	•	•
4000	16	•	•	•	•	•	•	•	•	•	•	•	•
5000	8	•	•	•	•	•	•	•	•	•	•	•	•
5000	12	•	•	•	•	•	•	•	•	•	•	•	•
5000	16	•	•	•	•	•	•	•	•	•	•	•	•
6000	12	•	•	•	•	•	•	•	•	•	•	•	•
6000	16	•	•	•	•	•	•	•	•	•	•	•	•
8000	8	•	•	•	•	•	•	•	•	•	•	•	•
8000	12	•	•	•	•	•	•	•	•	•	•	•	•
8000	16	•	•	•	•	•	•	•	•	•	•	•	•
10000	8	•	•	•	•	•	•	•	•	•	•	•	•
10000	12	•	•	•	•	•	•	•	•	•	•	•	•
10000	16	•	•	•	•	•	•	•	•	•	•	•	•

HIGH PRESSURE VESSELS



HIGH PRESSURE VESSELS

VERTICAL 21 BAR PAINTED - GALVANIZED

Directive	2014/29/UE(PED)	2014/68/UE(PED)
Operating pressure	21 bar	21 bar
Operating temperature	* -20 +120°C	-20 +100°C

2014/29/UE(PED)

Material
Carbon steel

Fluid content
Compressed air / Nitrogen (group 2)

Finishing
RAL 5015: External Ral 5015 blue paint (standard)
GALVANIZED: internal and external hot-dip galvanization

Upon request
ALM version



2014/68/UE(PED)

Material
Carbon steel

Fluid content
Compressed air / Nitrogen / Argon / Helium / Oil / Oxygen (group 1 hydrogen excluded)

Finishing
RAL 5015: External Ral 5015 blue paint (standard)
GALVANIZED: internal and external hot-dip galvanization

Upon request
ALM version



CODE	Directive	Capacity	Operating pressure	De	A	B	C	L	1	2	3	4	5	6	7	Weight
		lt	bar	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	inch	kg

RAL 5015*

VEC00883	2014/29/UE	*120	21	396	170	395	1065	1430	2"	3/4"	3/4"	1/4"	3/4"	3/4"	=	58
VEC02407	2014/29/UE	*270	21	500	170	600	1305	1790	2"	1"	1"	=	1"	=	=	108
VEC01470	2014/29/UE	*475	21	600	155	785	1665	2055	2"	2"	2"	=	3/8"	2"	2"	220
VEC02275	2014/68/UE(PED)	1000	21	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	352
VEC04155	2014/68/UE(PED)	3000	21	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	1250

GALVANIZED

VEC02438	2009/105/EC	*120	21	396	300	505	1175	1362	2"	3/4"	3/4"	1/4"	3/4"	3/4"	=	58
VEC02433	2009/105/EC	*270	21	500	170	600	1305	1790	2"	1"	1"	=	1"	=	=	110
VEC02434	2009/105/EC	*475	21	600	155	785	1665	2050	2"	2"	2"	=	3/8"	2"	2"	224
VEC02439	2014/68/UE(PED)	1000	21	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	352
VEC04156	2014/68/UE(PED)	3000	21	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	1250

HIGH PRESSURE VESSELS

VERTICAL 32 BAR
PAINTED - GALVANIZED


Material
Carbon steel

Fluid content
Compressed air / Nitrogen / Argon
/ Helium / Oil / Oxygen
(group 1 hydrogen excluded)

Finishing
RAL 5015: External Ral 5015 blue paint
(standard)
GALVANIZED: internal and external
hot-dip galvanization

Upon request
Inspection ports
100x150 mm handhole
300x400 mm manhole
Flanged connections
ALM version

Directive 2014/68/UE(PED)
Operating pressure 32 bar
Operating temperature -20 +100°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	L	1	2	3	4	5	6	7	Weight
		lt	bar	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	inch	kg

RAL 5015*

VEC02248	2014/68/UE(PED)	100	32	370	180	355	1055	1213	2"	3/4"	=	3/8"	3/8"	=	3/4"	89
VEC02249	2014/68/UE(PED)	270	32	500	175	599	1304	1648	2"	1"	1"	=	3/8"	1"	1"	192
VEC02250	2014/68/UE(PED)	500	32	600	155	785	1665	2050	2"	2"	2"	1/2"	1/2"	2"	2"	308
VEC02251	2014/68/UE(PED)	1000	32	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	470
VEC02252	2014/68/UE(PED)	1500	32	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	665
VEC02253	2014/68/UE(PED)	2000	32	1000	170	770	2185	2740	2"	2"	2"	1/2"	1/2"	2"	2"	1100
VEC02254	2014/68/UE(PED)	3000	32	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	1535
VEC02255	2014/68/UE(PED)	4000	32	1450	225	800	2145	2790	2"	3"	3"	3/4"	3/8"	3"	3"	1950
VEC02256	2014/68/UE(PED)	5000	32	1450	225	800	2745	3390	2"	3"	3"	3/4"	3/8"	3"	3"	2280
VEC02805	2014/68/UE(PED)	6000	32	1450	251	1000	2745	4053	2"	3"	3"	3/4"	3/8"	3"	3"	2700

GALVANIZED

VEC02440	2014/68/UE(PED)	100	32	370	180	355	1055	1213	2"	3/4"	=	3/8"	3/8"	=	3/4"	89
VEC02441	2014/68/UE(PED)	270	32	500	175	599	1304	1648	2"	1"	1"	=	3/8"	1"	1"	192
VEC02442	2014/68/UE(PED)	500	32	600	155	785	1665	2050	2"	2"	2"	1/2"	1/2"	2"	2"	308
VEC02443	2014/68/UE(PED)	1000	32	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	470
VEC02444	2014/68/UE(PED)	1500	32	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	665
VEC02446	2014/68/UE(PED)	2000	32	1000	170	770	2185	2740	2"	2"	2"	1/2"	1/2"	2"	2"	1100
VEC02447	2014/68/UE(PED)	3000	32	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	1535
VEC02448	2014/68/UE(PED)	4000	32	1450	225	800	2145	2790	2"	3"	3"	3/4"	3/8"	3"	3"	1950
VEC02450	2014/68/UE(PED)	5000	32	1450	225	800	2745	3390	2"	3"	3"	3/4"	3/8"	3"	3"	2280
VEC04704	2014/68/UE(PED)	6000	32	1450	251	1000	2745	4053	2"	3"	3"	3/4"	3/8"	3"	3"	2700

HIGH PRESSURE VESSELS

VERTICAL 42 BAR
PAINTED - GALVANIZED


Material
Carbon steel

Fluid content
Compressed air / Nitrogen / Argon
/ Helium / Oil / Oxygen
(group 1 hydrogen excluded)

Finishing
RAL 5015: External Ral 5015 blue paint
(standard)
GALVANIZED: internal and external hot-dip
galvanization

Upon request
Inspection ports
100x150 mm handhole
300x400 mm manhole
Flanged connections
ALM version

Directive 2014/68/UE(PED)
Operating pressure 42 bar
Operating temperature -20 +80°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	L	1	2	3	4	5	6	7	Weight
		lt	bar	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	inch	kg

RAL 5015*

VEC02262	2014/68/UE(PED)	100	42	370	180	355	1055	1213	2"	3/4"	=	3/8"	3/8"	=	3/4"	100
VEC02263	2014/68/UE(PED)	200	42	446	200	430	1255	1587	2"	1"	=	1/2"	3/8"	=	1"	150
VEC02264	2014/68/UE(PED)	270	42	500	175	599	1304	1648	2"	1"	1"	=	3/8"	1"	1"	215
VEC02265	2014/68/UE(PED)	500	42	600	155	785	1665	2050	2"	2"	2"	1/2"	1/2"	2"	2"	355
VEC02266	2014/68/UE(PED)	1000	42	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	675
VEC02267	2014/68/UE(PED)	1500	42	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	1100
VEC02268	2014/68/UE(PED)	2000	42	1100	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"	1460
VEC02269	2014/68/UE(PED)	3000	42	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	1950
VEC02270	2014/68/UE(PED)	4000	42	1450	225	800	2145	2790	2"	3"	3"	3/4"	3/8"	3"	3"	2540
VEC02271	2014/68/UE(PED)	5000	42	1450	225	800	2745	3390	2"	3"	3"	3/4"	3/8"	3"	3"	2845

GALVANIZED

VEC02452	2014/68/UE(PED)	100	42	370	180	355	1055	1213	2"	3/4"	=	3/8"	3/8"	=	3/4"	100
VEC02454	2014/68/UE(PED)	200	42	446	200	430	1255	1587	2"	1"	=	1/2"	3/8"	=	1"	150
VEC02455	2014/68/UE(PED)	270	42	500	175	599	1304	1648	2"	1"	1"	=	3/8"	1"	1"	215
VEC02456	2014/68/UE(PED)	500	42	600	155	785	1665	2050	2"	2"	2"	1/2"	1/2"	2"	2"	355
VEC02457	2014/68/UE(PED)	1000	42	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"	675
VEC02458	2014/68/UE(PED)	1500	42	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	1100
VEC02460	2014/68/UE(PED)	2000	42	1100	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"	1460
VEC02461	2014/68/UE(PED)	3000	42	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"	1950
VEC02462	2014/68/UE(PED)	4000	42	1450	225	800	2145	2790	2"	3"	3"	3/4"	3/8"	3"	3"	2540
VEC02463	2014/68/UE(PED)	5000	42	1450	225	800	2745	3390	2"	3"	3"	3/4"	3/8"	3"	3"	2845

ASME VESSELS

Material
Carbon steel / Stainless steel


Fluid content
Compressed air / Nitrogen / Argon / Helium / Oil / Oxygen (group 1 hydrogen excluded)

Finishing
In compliance with customer's requirements or our standard options (for more details see page 6)


Directive ASME SECTION VIII - DIVISION 1

Operating pressure Da 145 a 300 PSI

Operating temperature -20 +250°F



Capacity	De	A	B	C	L	1	2	3	4	5	6	7
It	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	inch
2000	1100	200	770	1970	2490	2"	2"	2"	1/2"	1/2"	2"	2"
3000	1200	140	830	2250	2990	2"	2"	2"	1/2"	1/2"	2"	2"
5000	1450	225	900	2745	3390	2"	3"	3"	3/4"	3/8"	3"	3"



Capacity	De	A	B	C	L	1	2	3	4	5	6	7
It	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	inch
270	500	175	599	1304	1648	2"	1"	1"	-	3/8"	1"	1"
500	600	155	785	1665	2050	2"	2"	2"	1/2"	1/2"	2"	2"
1000	800	145	770	1720	2350	2"	2"	2"	3/8"	3/8"	2"	2"

STAINLESS STEEL VESSELS



VERTICAL
STAINLESS STEEL


Material
Aisi 304/316L Stainless steel

Fluid content
Compressed air / Nitrogen /
Compressed air and water (group 2)

Finishing
Internal and external pickling
and passivation

Upon request
External electropolishing treatment

Directive 2014/68/UE(PED)
Operating pressure 11 bar
Operating temperature * -80 +120°C / -55 +80°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	L	1	2	3	4	5	6	7	Weight
		lt	bar	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	inch	inch	kg

AISI 304

VES03153	2014/68/UE(PED)	*24	11	240	40	161	553	772	1/2"	=	1/2"	=	=	1/2"	=	15
VES01881	2014/68/UE(PED)	*50	11	305	129	276	717	957	1/2"	1/2"	=	=	=	=	1/2"	21
VES01883	2014/68/UE(PED)	*100	11	370	170	358	948	1184	1/2"	=	3/4"	3/8"	3/8"	3/4"	=	32
VES03203	2014/68/UE(PED)	*150	11	446	165	400	897	1277	1/2"	1"	=	1/4"	=	=	1"	49
VES01885	2014/68/UE(PED)	*200	11	446	160	492	1192	1572	1/2"	=	1"	3/8"	3/8"	1"	=	55
VES01887	2014/68/UE(PED)	*270	11	500	165	560	1279	1771	1/2"	1"	1"	3/8"	3/8"	=	1"	69
VES01889	2014/68/UE(PED)	500	11	600	151	763	1633	2061	1/2"	1"	1"	=	3/8"	1"	1"	125
VES01891	97/23/EC (PED)	1000	11	800	140	702	1642	2346	2"	2"	2"	3/8"	3/8"	2"	2"	377
VES02812	2014/68/UE(PED)	1500	11	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	634
VES02773	2014/68/UE(PED)	2000	11	1100	170	740	1940	2460	2"	2"	2"	1/2"	1/2"	2"	2"	810
VES03787	2014/68/UE(PED)	3000	11	1200	150	878	220	2871	2"	2"	2"	1/2"	1/2"	2"	2"	942

AISI 316L

VES03155	2014/68/UE(PED)	*24	11	240	40	161	553	772	1/2"	=	1/2"	=	=	1/2"	=	15
VES01882	2014/68/UE(PED)	*50	11	305	129	276	717	957	1/2"	1/2"	=	=	=	=	1/2"	21
VES01884	2014/68/UE(PED)	*100	11	370	140	298	948	1106	1/2"	3/4"	=	3/8"	3/8"	=	3/4"	32
VES03204	2014/68/UE(PED)	*150	11	446	165	400	897	1277	1/2"	1"	=	1/4"	=	=	1"	49
VES01886	2014/68/UE(PED)	*200	11	446	160	492	1192	1572	1/2"	=	1"	3/8"	3/8"	1"	=	55
VES01888	2014/68/UE(PED)	*270	11	500	165	560	1279	1771	1/2"	1"	1"	3/8"	3/8"	=	1"	69
VES01890	2014/68/UE(PED)	500	11	600	151	763	1633	2061	1/2"	1"	1"	=	3/8"	1"	1"	125
VES01892	97/23/EC (PED)	1000	11	800	140	702	1642	2346	2"	2"	2"	3/8"	3/8"	2"	2"	377
VES02813	2014/68/UE(PED)	1500	11	1000	170	680	1780	2305	2"	2"	2"	1/2"	1/2"	2"	2"	634
VES02774	2014/68/UE(PED)	2000	11	1100	170	740	1940	2460	2"	2"	2"	1/2"	1/2"	2"	2"	810
VES03788	2014/68/UE(PED)	3000	11	1200	150	878	220	2871	2"	2"	2"	1/2"	1/2"	2"	2"	942

HORIZONTAL
STAINLESS STEEL


Material
Aisi 304/316L Stainless steel

Fluid content
Compressed air / Nitrogen /
Compressed air and water (group 2)

Finishing
Internal and external pickling
and passivation

Upon request
External electropolishing treatment

Directive 2014/68/UE(PED)
Operating pressure 11 bar
Operating temperature * -80 +120°C / -55 +80°C



CODE	Directive	Capacity	Operating pressure	De	A	B	C	E	F	H	a	b	c	d	x	y	k	j	z	Weight
		lt	bar	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	mm	inch	inch	inch	inch	inch	kg

AISI 304

VES04028	2014/68/UE(PED)	*5	11	150	314	130	45	100	160	125	=	=	=	110	1/2"	=	=	=	1/2"	6
VES02586	2014/68/UE(PED)	*10	12	169	506	156	127	200	140	170	127	-	127	205	1/2"	-	1/2"	-	1/2"	8
VES02588	2014/68/UE(PED)	*15	12	196	624	156	172	200	140	178	172	-	172	250	1/2"	-	1/2"	-	1/2"	11
VES02590	2014/68/UE(PED)	*24	11	240	634	192	150	240	180	210	100	-	100	246	1/2"	-	1/2"	-	1/2"	13
VES02592	2014/68/UE(PED)	*50	11	305	784	400	100	285	236	200	100	-	100	300	1/2"	3/8"	3/8"	-	1/2"	21
VES02594	2014/68/UE(PED)	*100	11	370	966	550	100	352	306	256	45	80	45	45	1/2"	3/8"	1/2"	3/8"	3/8"	32
VES03205	2014/68/UE(PED)	*150	11	446	1064	450	175	440	386	288	50	150	50	50	1/2"	3/8"	1/2"	3/8"	1/2"	49
VES02596	2014/68/UE(PED)	*200	11	446	1364	750	175	440	386	288	50	150	50	50	1/2"	3/8"	1/2"	1/2"	3/8"	55
VES02598	2014/68/UE(PED)	*270	11	500	1558	900	175	463	409	315	50	150	120	50	1/2"	3/8"	1"	1/2"	1/2"	69
VES02600	2014/68/UE(PED)	500	11	600	1864	1204	148	530	470	396	60	155	60	60	1/2"	3/8"	1"	1/2"	1/2"	125
VES02602	2014/68/UE(PED)	1000	11	800	2144	1010	345	605	440	500	100	155	60	60	2"	3/4"	1"	1/2"	1/2"	377

AISI 316L

VES04026	2014/68/UE(PED)	*5	11	150	314	130	45	100	160	125	=	=	=	110	1/2"	=	=	=	1/2"	6
VES02587	2014/68/UE(PED)	*10	12	169	506	156	127	200	140	170	127	-	127	205	1/2"	-	1/2"	-	1/2"	8
VES02589	2014/68/UE(PED)	*15	12	196	624	156	172	200	140	178	172	-	172	250	1/2"	-	1/2"	-	1/2"	11
VES02591	2014/68/UE(PED)	*24	11	240	634	192	150	240	180	210	100	-	100	246	1/2"	-	1/2"	-	1/2"	13
VES02593	2014/68/UE(PED)	*50	11	305	784	400	100	285	236	200	100	-	100	300	1/2"	3/8"	3/8"	-	1/2"	21
VES02595	2014/68/UE(PED)	*100	11	370	966	550	100	352	306	256	45	80	45	45	1/2"	3/8"	1/2"	3/8"	3/8"	32
VES03206	2014/68/UE(PED)	*150	11	446	1064	450	175	440	386	288	50	150	50	50	1/2"	3/8"	1/2"	3/8"	1/2"	49
VES02597	2014/68/UE(PED)	*200	11	446	1364	750	175	440	386	288	50	150	50	50	1/2"	3/8"	1/2"	1/2"	3/8"	55
VES02599	2014/68/UE(PED)	*270	11	500	1558	900	175	463	409	315	50	150	120	50	1/2"	3/8"	1"	1/2"	1/2"	69
VES02601	2014/68/UE(PED)	500	11	600	1864	1204	148	530	470	396	60	155	60	60	1/2"	3/8"	1"	1/2"	1/2"	125
VES02603	2014/68/UE(PED)	1000	11	800	2144	1010	345	605	440	500	100	155	60	60	2"	3/4"	1"	1/2"	1/2"	377

pressure gauge
Ø 63 mm
G 1/4"

ball tap
G 1/2"
G 1"

pressure gauge flange
G 3/8"

safety valve
G 1/2" connection

safety valve
G 1/2" connection

safety valve
G 1" connection

safety valve
G 1" connection

safety valve
G 3/4" connection

pressure gauge
Ø 63 mm
G 1/4"

ball tap
G 1/2"
G 1"

pressure gauge flange
G 3/8"

safety valve
G 1/2" connection

safety valve
G 1/2" connection

safety valve
G 1" connection

safety valve
G 1" connection


safety valve
G 3/4" connection

ACCESSORIES


CODE	Unit	Description	Material	Directive	Calibration	Drain flow rate
KIT00024	1 1	Safety valve with G 1/2" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	11 bar 11 bar	7237 Lt/min
KIT00100	1 1 1	Safety valve with G 3/4" connection Ø 63 mm G 1/4" pressure gauge G 1/2" ball tap	BRASS	2014/68/UE(PED)	11 bar 11 bar	17767 Lt/min
KIT00093	1 1 1	Safety valve with G 1" connection Ø 63 mm G 1/4" pressure gauge G 1" ball tap	BRASS	2014/68/UE(PED)	11 bar 11 bar	38221 Lt/min
KIT00026	1 1 1	Safety valve with G 3/4" connection Ø 63 mm G 1/4" pressure gauge G 1/2" ball tap	BRASS	2014/68/UE(PED)	12 bar 12 bar	19184 Lt/min
KIT00028	1 1 1	Safety valve with G 1" connection Ø 63 mm G 1/4" pressure gauge G 1" ball tap	BRASS	2014/68/UE(PED)	12 bar 12 bar	41407 Lt/min
KIT00114	1 1	Safety valve with G 1/2" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	15 bar 15 bar	9650 Lt/min
KIT00031	1 1	Safety valve with G 1/2" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	16 bar 16 bar	10253 Lt/min
KIT00088	1 1	Safety valve with G 3/4" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	16 bar 16 bar	24851 Lt/min
KIT00023	1 1	Safety valve with G 1" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	16 bar 16 bar	54147 Lt/min
KIT00040	1 1	Safety valve with G 1/2" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	21 bar 25 bar	16517 Lt/min
KIT00105	1 1	Safety valve with G 1/2" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	32 bar 32 bar	24811 Lt/min
KIT00106	1 1	Safety valve with G 1" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	32 bar 32 bar	103110 Lt/min
KIT00107	1 1	Safety valve with G 1/2" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	42 bar 42 bar	32350 Lt/min
KIT00087	1 1	Safety valve with G 1" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	42 bar 42 bar	134442 Lt/min
KIT00030	1 1	Safety valve with G 1/2" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	8 bar 8 bar	5419 Lt/min
KIT00102	1 1	Safety valve with G 1" connection Ø 63 mm G 1/4" pressure gauge	BRASS	2014/68/UE(PED)	8 bar 8 bar	28666 Lt/min
KIT00044	1 1	Safety valve with G 1/2" connection Ø 63 mm G 1/4" pressure gauge	316L STAINLESS STEEL	2014/68/UE(PED)	11 bar 11 bar	8983 Lt/min
KIT00103	1 1	Safety valve with G 1" connection Ø 63 mm G 1/4" pressure gauge	316L STAINLESS STEEL	2014/68/UE(PED)	11 bar 11 bar	37317 Lt/min
ART00122	1 1	Pressure gauge flange with G 3/8" connection	BRASS	=====	===	-

INSTALLATIONS

COMPRESSED AIR PLANT EXAMPLE



AUTOCLAVE PLANT EXAMPLE



SPECIAL PROJECTS

We closely cooperate with our customers during activities of research and development, supporting their quality and specification requirements with a view to ideal product integration in the system where our vessels are to be installed.

We ensure the utmost care and attention to customized design projects in accordance with customer specifications and instructions, e.g., special flange mounting requirements, manual welding or customized carpentries.



